
Appendix 5A

Sample Government M&R Projects

Project	Estimated Cost
Replace deteriorated entrance/fee station bulletin boards and supporting structures per FS specifications (5 panels).	\$1,125
Replace campground information orientation sign at entrance/fee station with fiberglass-embedded signs per FS design and specifications. FS will provide camera-ready design.	2,500
Rehabilitate trails accessing Campsites 8, 9, and 10.	825
Install Class 6 rock rip-rap for erosion control at end of and along parking spur at Campsite 21.	1,320
Convert Campsites 20 and 21 into a two-family, accessible campsite per FS specifications. Relocate one table and one pedestal grill. Level pad at Campsite 21. Construct accessible route to site, and sign as accessible.	1,335
Relocate Campsite 32 to shady area. Replace table, fire ring, and pedestal grill with accessible furnishings. Level campsite, and construct accessible route.	1,135
Replace double gate on main road to upper loops.	1,500
Remove post-and-rail barrier in parking spur for Campsite 59 and rock spur.	250
Replace existing grills with accessible pedestal grills at Campsites 26, 29, 44, 47-53, and 58.	1,800
Replace rip-rap and culvert at washed-out road near Campsite 6.	1,000
Level ground around fire rings, pedestal grills, and table pads at 22 campsites.	2,400
Replace worn-out group cooking stoves and grills with group pedestal grills at Group Campsites 1, 2, and 3.	2,700
Repair and/or replace three wash racks (one per group campsite) with drainage sumps for improved sanitation.	3,300
Remove existing pit toilet and replace with single-unit, accessible SST.	13,000

Appendix 5A: Sample Government M&R Projects

Project	Estimated Cost
Replace two pit toilets with two sealed-vault toilets, using FS SST design and specifications.	18,000
Replace two unadaptable vault toilets with accessible, 60-inch-turning-radius models using FS design and specifications.	25,000
Weed-treat (as preparation for paving) and repave 40,000-square-foot parking lot.	40,000